BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK: Construction Of CC Roads & Drains Opp Govt Hospital Mallasandra In Ward-14 Bagalagunte Dasarahalli Sub Division

SI No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 141/ Item No. 19.1/ PWD SR 2015-16.	Cum	160.00	83.16	Eighty Three Rupees And Sixteen Paise Only
2	KSRRB 300-50 Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per Specification Morth / Chapter .3 Page No.146, Item No.19.56 / PWD SR.2015-16	Sqm	1611.00	30.24	Thirty Rupees And Twenty Four Paise Only
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 Page No.12/ Item No. 4.3/ PWD SR 2015-16	Cum	263.25	5070.60	Five Thousand Seventy Rupees And Sixty Paise Only
4	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.5 ,P.13/I.4.11/ PWD SR 2015-16	Cum	124.20	6198.12	Six Thousand One Hundred Ninty Eight Rupees And Twelve Paise Only
5	Providing & laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregate of ready mixed concrete RMC M20 for RCC works laid in 15cm thick layers and well compacted vibrating,curing,for raft foundation column footing,main and secondary beams with all lead and lift etc,complete (exclusive of cost of steel and fabrication charges Page No.18/ Item No. 4.48/ PWD SR 2015-16	Qty	74.52	6980.58	Six Thousand Nine Hundred Eighty Rupees And Fifty Eight Paise Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

6	Providing & laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregate of ready mixed concrete RMC M20 for RCC works laid in 15cm thick layers and well compacted vibrating,curing,for raft foundation column footing,main and secondary beams with all lead and lift etc,complete (exclusive of cost of steel and fabrication charges Page No.18/ Item No. 4.48/ PWD SR 2015-16	Qty	209.43	6332.04	Six Thousand Three Hundred And Thirty Two And Four Paise Only
7	KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. Specification No. KSRB 4.6.9. exceeding 1m in depth. Page No. 15/ Item No. 4.31/ PWD SR 2015-16	Sqm	736.00	306.72	Three Hundred And six Rupees Ad Seventy Two paise Only
8	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	207.00	1600.00	One Thousand Six hundred Rupees Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 68.00 (P.133 I.18.57/1) 2015-16	Cum	160.00	81.73	Eighty One Rupees Seventy Three Paise Only

Signature Of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,

6	Providing & laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregate of ready mixed concrete RMC M20 for RCC works laid in 15cm thick layers and well compacted vibrating,curing,for raft foundation column footing,main and secondary beams with all lead and lift etc,complete (exclusive of cost of steel and fabrication charges Page No.18/ Item No. 4.48/ PWD SR 2015-16	Qty	209.43	6332.04	Six Thousand Three Hundred And Thirty Two And Four Paise Only
7	KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. Specification No. KSRB 4.6.9. exceeding 1m in depth. Page No. 15/ Item No. 4.31/ PWD SR 2015-16	Sqm	736.00	306.72	Three Hundred And six Rupees Ad Seventy Two paise Only
8	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	207.00	1600.00	One Thousand Six hundred Rupees Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 68.00 (P.133 I.18.57/1) 2015-16	Cum	160.00	81.73	Eighty One Rupees Seventy Three Paise Only

Signature Of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,